
DETERMINING THE FORESHORTENED DEPTH OF A ROOM

The following diagrams illustrate a simple and fairly accurate method of determining the depth of a room in a single-point perspective drawing.

- STEP No. 1 Draw the frame of the picture plane and mark out the front edges of the first row of tiles.
- STEP No. 2 Locate the vanishing point and draw the horizon line.
- STEP No. 3 Draw orthogonal lines from the edges of the tiles and converging to the vanishing point.



Date: 21st January 2015

STEP No.4 Draw a faint diagonal from point C (intersection between eye-level line and the picture frame) to point A (room corner).


STEP No.5 Draw a quadrant radius AB.

STEP No.6 Mark the point of intersection between the diagonal and the quadrant.

STEP No.7 Draw a horizontal line passing through the intersection. This line represents the first row of tiles.

Note: In practice only a short line is necessary starting from point A and directing towards point C .

STEP No.8 Line in the left hand corner tile (marked blue).




STEP No.9 Draw a diagonal from point A to the corner of the tile and extent to the right-hand orthogonal.

STEP No.10 Draw transversals at the points of intersections between the orthogonals and the diagonal.

Notes: a) If the room has a square floor area, all transversals are to be drawn.

- b) If the room has a rectangular floor area and the wider part of the room is facing the viewer, less transversals are required.
- c) If the room has a rectangular floor area and the narrower part of the room is facing the viewer, refer to the method shown on the next page.



STEP No.11 Choose any tile in the middle of the floor area and draw a diagonal from corner to corner (marked in red).

STEP No.12 Extend the diagonal to the right-hand orthogonal.

STEP No.13 Draw as many additional transversals as required.

Note: If more transversals are required, repeat steps 11, 12 and 13.

